

# 実行予算書

集計日：2016/09/30

			

No	1	状 況	契約
見 積 日	2015/7/1	担 当 者	昭和 一郎
顧 客 名	甲府建設株式会社	設 計 者	
見 積 先	甲府 二郎 様	契 約 日	
工 事 名	サンプル設備工事	着 工 日	
工 事 場 所	甲府市丸の内3-28-9	竣 工 日	
見積有効期限	お見積後30日	予 算 提 出 日	
納 入 期 日		予 算 承 認 日	
御 支 払 条 件	工事請負契約書の通り		
備 考			
見 積 書 メ モ		実行予算メモ	

	見 積 金 額	実 行 金 額	注 文 金 額	予 算 残 高	実行粗利益	利益率	注文粗利益	利益率
工 事 計	700,000	610,000	123,000	487,000	90,000	13	577,000	82
法 定 福 利 費	23,738	20,686						
税 抜 金 額	723,738	630,686	123,000	507,686	93,052	13	600,738	83
消 費 税	57,899	50,455	9,840					
税 後 値 引								
税 込 金 額	781,637	681,141	132,840	548,301	100,496	13	648,797	83

No	項目	規格・摘要	見積数量	実行数量	単位	見積単価	実行単価	注文数量	単位	注文単価	見積金額	実行金額	注文金額	予算残高	見積備考	注文備考	No	予定発注先	No	発注先	注文No	注文日	見積非税	注文非税
	給水設備工事		1	1	式						101,000	87,000	87,000				04	昭和設備 株式会社	04	昭和設備 株式会社	1-001	2015/07/10		
	給湯設備工事		1	1	式						43,000	36,000	36,000				04	昭和設備 株式会社	04	昭和設備 株式会社	1-001	2015/07/10		
	排水設備工事		1	1	式						395,000	324,000		324,000										
	衛生器具設備工事		1	1	式						113,000	93,000		93,000										
	給水管引込工事		1	1	式						140,000	127,000		127,000										
	現場雑費		1	1	式	8,000	7,000				8,000	7,000		7,000										
	諸経費	上、下水道申請費を含む	1	1	式	80,000	66,000				80,000	66,000		66,000										
	値引き		1	1	式	-130,000	-130,000				-130,000	-130,000		-130,000										
※	別途費用																							
	水道利用加入金	136,500円																						
	設計審査手数料・竣工検査手数料	8,700円																						
	[値引]										-50,000													
	[工事計]										700,000	610,000	123,000	487,000										
	[法定福利費]										23,738	20,686												
	[合計]										723,738	630,686	123,000	507,686										
	[消費税]										57,899	50,455	9,840											
	[税込み合計]										781,637	681,141	132,840	548,301										





No	項目	規格・摘要	見積数量	実行数量	単位	見積単価	実行単価	注文数量	単位	注文単価	見積金額	実行金額	注文金額	予算残高	見積備考	注文備考	No	予定発注先	No	発注先	注文No	注文日	見積非税	注文非税
	配管材料費																							
	硬質塩ビ管	VU100	44	44	m	546	436				24,024	19,184		19,184										
	硬質塩ビ管	VU75	20	20	m	364	302				7,280	6,040		6,040										
	硬質塩ビ管	VU50	15	15	m	186	169				2,790	2,535		2,535										
	配管用継手材料費		1	1	式	24,000	22,000				24,000	22,000		22,000										
	管支持金物		1	1	式	7,500	7,000				7,500	7,000		7,000										
	小口径汚水桝	100-150	3	3	組	3,580	3,000				10,740	9,000		9,000										
	トラップ桝	300	2	2	組	3,180	2,800				6,360	5,600		5,600										
	雨水桝	300	4	4	組	2,572	2,300				10,288	9,200		9,200										
	屋内配管工事費																							
	硬質塩ビ管(屋内)	VU75	2	2	m	3,990	3,192				7,980	6,384		6,384										
	硬質塩ビ管(屋内)	VU50	13	13	m	2,660	2,128				34,580	27,664		27,664										
	屋外配管工事費																							
	硬質塩ビ管(屋外)	VU100	44	44	m	3,230	2,584				142,120	113,696		113,696										
	硬質塩ビ管(屋外)	VU75	18	18	m	2,470	1,976				44,460	35,568		35,568										
	硬質塩ビ管(屋外)	VU50	2	2	m	1,710	1,368				3,420	2,736		2,736										
	小口径汚水桝取付費	100-150	3	3	ヶ所	6,000	4,800				18,000	14,400		14,400										
	トラップ桝取付費	300	2	2	ヶ所	6,000	4,800				12,000	9,600		9,600										
	雨水桝取付費	300	4	4	ヶ所	6,000	4,800				24,000	19,200		19,200										
	消耗品雑材料費		1	1	式	15,458	14,193				15,458	14,193		14,193										
	[小計]										395,000	324,000		324,000										



No	項目	規格・摘要	見積数量	実行数量	単位	見積単価	実行単価	注文数量	単位	注文単価	見積金額	実行金額	注文金額	予算残高	見積備考	注文備考	No	予定発注先	No	発注先	注文No	注文日	見積非税	注文非税
	配管材料費																							
	VP用ボール式ナット分水栓	75X20	1	1	個	10,036	8,492				10,036	8,492		8,492										
	伸縮可とう継手	20	4	4	個	4,080	3,600				16,320	14,400		14,400										
	逆止弁付ボール止水栓	20	1	1	個	8,952	7,833				8,952	7,833		7,833										
	メーターBOX	20	1	1	個	5,280	4,800				5,280	4,800		4,800										
	ブロック		2	2	個	130	100				260	200		200										
	SGP-VB	20	3	3	m	890	763				2,670	2,289		2,289										
	HIVP	20	2	2	m	178	156				356	312		312										
	配管工事費																							
	分岐掘削工	75X20	1	1	ヶ所	29,500	29,500				29,500	29,500		29,500										
	分水栓取付工	75X20	1	1	ヶ所	2,490	2,490				2,490	2,490		2,490										
	管布設工(全面入替)	H=0.6 20	2	2	m	5,900	5,900				11,800	11,800		11,800										
	布設工	SGP-VB 20	3	3	m	3,600	2,880				10,800	8,640		8,640										
	ポリスリーブ取付工	75	1	1	ヶ所	390	390				390	390		390										
	止水栓取付工(BOX据付を含む)	20	1	1	ヶ所	1,500	1,500				1,500	1,500		1,500										
	擁壁穴明け費		2	2	ヶ所	3,000	2,400				6,000	4,800		4,800										
	保温工事費		1	1	式	4,500	4,000				4,500	4,000		4,000										
	埋設シート設置工		1	1	m	220	220				220	220		220										
	舗装切断工		4	4	m	360	360				1,440	1,440		1,440										
	舗装撤去工		1	1	式	4,000	3,200				4,000	3,200		3,200										
	舗装処理費		1	1	式	1,500	1,200				1,500	1,200		1,200										
	交通整理員		1	1	人工	14,000	12,000				14,000	12,000		12,000										
	消耗品雑材料費		1	1	式	3,686	3,194				3,686	3,194		3,194										
	占用届		1	1	件	4,300	4,300				4,300	4,300		4,300										
	[小計]										140,000	127,000		127,000										