

実行予算書

		昭和

No	1		① 見積金額	② 実行予算	利益率	①-② 粗利益
状 況		税 抜 金 額	858,145	765,094	10.84	93,051
見 積 日	2021/1/9	消 費 税	85,815	76,509		
顧 客 名	甲府建設株式会社	税 後 値 引				
見 積 先	甲府 二郎 様	税 込 金 額	943,960	841,603	10.84	102,357
工 事 名	サンプル設備工事	備 考				
工 事 場 所	甲府市丸の内3-28-9					
見積有効期限	お見積後30日					
納 入 期 日						
御 支 払 条 件	工事請負契約書の通り					
		メ モ	1回目			
担 当 者	昭和 一郎					

No	項目	規格・摘要	見積数量	実行数量	単位	定価	値引率	仕切率	見積単価	実行単価	見積金額	実行金額	粗利益	利益率	備考
	配管材料費														
	硬質塩ビ管	VU100	44	44	m				546	436	24,024	19,184	4,840	20.15	
	硬質塩ビ管	VU75	20	20	m				364	302	7,280	6,040	1,240	17.03	
	硬質塩ビ管	VU50	15	15	m				186	169	2,790	2,535	255	9.14	
	配管用継手材料費		1	1	式						24,000	22,000	2,000	8.33	
	管支持金物		1	1	式						7,500	7,000	500	6.67	
	小口径汚水柵	100-150	3	3	組				3,580	3,000	10,740	9,000	1,740	16.20	
	トラップ柵	300	2	2	組				3,180	2,800	6,360	5,600	760	11.95	
	雨水柵	300	4	4	組				2,572	2,300	10,288	9,200	1,088	10.58	
	屋内配管工事費														
	硬質塩ビ管(屋内)	VU75	2	2	m				3,990	3,192	7,980	6,384	1,596	20.00	
	硬質塩ビ管(屋内)	VU50	13	13	m				2,660	2,128	34,580	27,664	6,916	20.00	
	屋外配管工事費														
	硬質塩ビ管(屋外)	VU100	44	44	m				3,230	2,584	142,120	113,696	28,424	20.00	
	硬質塩ビ管(屋外)	VU75	18	18	m				2,470	1,976	44,460	35,568	8,892	20.00	
	硬質塩ビ管(屋外)	VU50	2	2	m				1,710	1,368	3,420	2,736	684	20.00	
	小口径汚水柵取付費	100-150	3	3	ヶ所				6,000	4,800	18,000	14,400	3,600	20.00	
	トラップ柵取付費	300	2	2	ヶ所				6,000	4,800	12,000	9,600	2,400	20.00	
	雨水柵取付費	300	4	4	ヶ所				6,000	4,800	24,000	19,200	4,800	20.00	
	消耗品雑材料費		1	1	式						15,458	14,193	1,265	8.18	
	[小計]										395,000	324,000	71,000	17.97	

No	項目	規格・摘要	見積数量	実行数量	単位	定価	値引率	仕切率	見積単価	実行単価	見積金額	実行金額	粗利益	利益率	備考
	配管材料費														
	VP用ボール式ダブル分水栓	75X20	1	1	個						10,036	8,492	1,544	15.38	
	伸縮可とう継手	20	4	4	個				4,080	3,600	16,320	14,400	1,920	11.76	
	逆止弁付ボール止水栓	20	1	1	個						8,952	7,833	1,119	12.50	
	メーターBOX	20	1	1	個						5,280	4,800	480	9.09	
	ブロック		2	2	個				130	100	260	200	60	23.08	
	SGP-VB	20	3	3	m				890	763	2,670	2,289	381	14.27	
	HIVP	20	2	2	m				178	156	356	312	44	12.36	
	配管工事費														
	分岐掘削工	75X20	1	1	ヶ所						29,500	29,500			
	分水栓取付工	75X20	1	1	ヶ所						2,490	2,490			
	管布設工(全面入替)	H=0.6 20	2	2	m				5,900	5,900	11,800	11,800			
	布設工	SGP-VB 20	3	3	m				3,600	2,880	10,800	8,640	2,160	20.00	
	ポリスリーブ取付工	75	1	1	ヶ所						390	390			
	止水栓取付工(BOX据付を含む)	20	1	1	ヶ所						1,500	1,500			
	擁壁穴明け費		2	2	ヶ所				3,000	2,400	6,000	4,800	1,200	20.00	
	保温工事費		1	1	式						4,500	4,000	500	11.11	
	埋設シート設置工		1	1	m						220	220			
	舗装切断工		4	4	m				360	360	1,440	1,440			
	舗装撤去工		1	1	式						4,000	3,200	800	20.00	
	舗装処理費		1	1	式						1,500	1,200	300	20.00	
	交通整理員		1	1	人工						14,000	12,000	2,000	14.29	
	消耗品雑材料費		1	1	式						3,686	3,194	492	13.35	
	占用届		1	1	件						4,300	4,300			
	[小計]										140,000	127,000	13,000	9.29	