



No	項目	規格・摘要	数量	単位	単価	金額	備考
	<b>給水設備工事</b>						
	配管材料費						
	耐衝撃性硬質塩ビ管	HIVP20	24	m	177	4,248	
	耐衝撃性硬質塩ビ管	HIVP13	12	m	99	1,188	
	架橋ポリエチレン管	13A 保温厚3mm	24	m	258	6,192	
	配管用継手材料費		1	式		18,500	
	管支持金物		1	式		1,872	
	屋内配管工事費						
	耐衝撃性硬質塩ビ管(屋内)	HIVP 20	1	m		1,330	
	架橋ポリエチレン管	13A	24	m	800	19,200	
	屋外配管工事費						
	耐衝撃性硬質塩ビ管(屋外)	HIVP 20	23	m	800	18,400	
	根切り埋戻し費		1	式		28,000	
	消耗品雑材料費		1	式		2,070	
	[小計]					101,000	
	<b>給湯設備工事</b>						
	配管材料費						
	架橋ポリエチレン管	13A	19	m	800	15,200	
	配管用継手材料費		1	式		9,800	
	管支持金物		1	式		1,200	
	配管工事費						
	架橋ポリエチレン管	13A	19	m	800	15,200	
	消耗品雑材料費		1	式		1,600	
	[小計]					43,000	
	<b>排水設備工事</b>						
	配管材料費						
	硬質塩ビ管	VU100	44	m	546	24,024	
	硬質塩ビ管	VU75	20	m	364	7,280	
	硬質塩ビ管	VU50	15	m	186	2,790	
	配管用継手材料費		1	式		24,000	
	管支持金物		1	式		7,500	
	小口径汚水枡	100-150	3	組	3,580	10,740	
	トラップ枡	300	2	組	3,180	6,360	
	雨水枡	300	4	組	2,572	10,288	
	屋内配管工事費						
	硬質塩ビ管(屋内)	VU75	2	m	3,990	7,980	
	硬質塩ビ管(屋内)	VU50	13	m	2,660	34,580	
	屋外配管工事費						
	硬質塩ビ管(屋外)	VU100	44	m	3,230	142,120	
	硬質塩ビ管(屋外)	VU75	18	m	2,470	44,460	

No	項目	規格・摘要	数量	単位	単価	金額	備考
	硬質塩ビ管(屋外)	VU50	2	m	1,710	3,420	
	小口径汚水柵取付費	100-150	3	ヶ所	6,000	18,000	
	トラップ柵取付費	300	2	ヶ所	6,000	12,000	
	雨水柵取付費	300	4	ヶ所	6,000	24,000	
	消耗品雑材料費		1	式		15,458	
	[小計]					395,000	
	<b>衛生器具設備工事</b>						
	ガーデンパン及び水栓柱	W=450, 900L	1	組		11,330	
	ガーデンパン及び水栓柱取付費		1	組		6,000	
	散水栓	散水栓BOX, T27NH13	1	組		3,580	
	散水栓取付費	散水栓BOX, T27NH13	1	組		4,500	
	洗濯機用水栓取付費		1	個		4,000	
	洗濯機パン取付費		1	個		10,000	
	洋風便器取付費		1	組		14,000	
	紙巻器取付費		1	個		2,500	
	洗面化粧台取付費		1	組		10,000	
	ユニットバス接続費		1	台		8,000	
	流し台接続費		1	組		5,000	
	エコキュート取付費		1	台		25,000	
	消耗品雑材料費		1	式		9,090	
	[小計]					113,000	
	<b>給水管引込工事</b>						
	配管材料費						
	VP用ボール式ボール分水栓	75X20	1	個		10,036	
	伸縮可とう継手	20	4	個	4,080	16,320	
	逆止弁付ボール止水栓	20	1	個		8,952	
	メーターBOX	20	1	個		5,280	
	ブロック		2	個	130	260	
	SGP-VB	20	3	m	890	2,670	
	HIVP	20	2	m	178	356	
	配管工事費						
	分岐掘削工	75X20	1	ヶ所		29,500	
	分水栓取付工	75X20	1	ヶ所		2,490	
	管布設工(全面入替)	H=0.6 20	2	m	5,900	11,800	
	布設工	SGP-VB 20	3	m	3,600	10,800	
	ポリスリーブ取付工	75	1	ヶ所		390	
	止水栓取付工(BOX据付を含む)	20	1	ヶ所		1,500	
	擁壁穴明け費		2	ヶ所	3,000	6,000	
	保温工事費		1	式		4,500	
	埋設シート設置工		1	m		220	
	舗装切断工		4	m	360	1,440	
	舗装撤去工		1	式		4,000	
	舗装処理費		1	式		1,500	
	交通整理員		1	人工		14,000	

No	項目	規格・摘要	数量	単位	単価	金額	備考
	消耗品雑材料費		1	式		3,686	
	占用届		1	件		4,300	
	[小計]					140,000	