

実行予算書

集計日：2024/06/30

No	4	状 況	契約
見 積 日	2024/5/15	担 当 者	昭和 一郎
顧 客 名	甲府建設株式会社 御中		
見 積 先	甲府 二郎 様	契 約 日	
工 事 名	サンプル設備工事	着 工 日	
工 事 場 所	山梨県甲府市	竣 工 日	
見積有効期限	お見積後30日	予 算 提 出 日	
納 入 期 日			
御 支 払 条 件	工事請負契約書の通り		
備 考			
見 積 書 メ モ	2回目	実行予算メモ	

	見 積 金 額	実 行 金 額	注 文 金 額	予 算 残 高	実行粗利益	利益率	注文粗利益	利益率
工 事 計	791,346	740,000	216,000	524,000	51,346	6	575,346	73
法 定 福 利 費	26,836	25,094						
税 抜 金 額	818,182	765,094	216,000	549,094	53,088	6	602,182	74
消 費 税	81,818	76,509	21,600					
税 後 値 引								
税 込 金 額	900,000	841,603	237,600	604,003	58,397	6	662,400	74

No	項目	規格・摘要	実行 数量	単位	注文 数量	単位	実行金額	注文金額	予算残高	発注先	注文No	注文日
	給水設備工事		1	式			87,000	87,000		昭和設備 株式会社	4-001	2024/05/23
	給湯設備工事		1	式			36,000	36,000		昭和設備 株式会社	4-001	2024/05/23
	排水設備工事		1	式			324,000		324,000			
	衛生器具設備工事		1	式			93,000	93,000		○×建設 株式会社	4-002	2024/05/24
	給水管引込工事		1	式			127,000		127,000			
	現場雑費		1	式			7,000		7,000			
	諸経費	上、下水道申請費を含む	1	式			66,000		66,000			
※	別途費用											
	水道利用加入金	136,500円										
	設計審査手数料・竣工検査手数料	8,700円										
	[値 引]											
	[工 事 計]						740,000	216,000	524,000			
	[法定福利費]						25,094					
	[合 計]						765,094	216,000	549,094			
	[消 費 税]						76,509	21,600				
	[税込み合計]						841,603	237,600	604,003			

No	項目	規格・摘要	実行数量	単位	注文数量	単位	実行金額	注文金額	予算残高	発注先	注文No	注文日
	配管材料費									昭和設備 株式会社	4-001	2024/05/23
	耐衝撃性硬質塩ビ管	HIVP20	22	m	22	m	3,542	3,542		昭和設備 株式会社	4-001	2024/05/23
	耐衝撃性硬質塩ビ管	HIVP13	12	m	12	m	1,080	1,080		昭和設備 株式会社	4-001	2024/05/23
	架橋ポリエチレン管	13A 保温厚3mm	24	m	24	m	5,568	5,568		昭和設備 株式会社	4-001	2024/05/23
	配管用継手材料費		1	式	1	式	18,000	18,000		昭和設備 株式会社	4-001	2024/05/23
	管支持金物		1	式	1	式	1,810	1,810		昭和設備 株式会社	4-001	2024/05/23
										昭和設備 株式会社	4-001	2024/05/23
	屋内配管工事費									昭和設備 株式会社	4-001	2024/05/23
	耐衝撃性硬質塩ビ管(屋内)	HIVP 20	1	m	1	m	1,064	1,064		昭和設備 株式会社	4-001	2024/05/23
	架橋ポリエチレン管	13A	24	m	24	m	15,360	15,360		昭和設備 株式会社	4-001	2024/05/23
										昭和設備 株式会社	4-001	2024/05/23
	屋外配管工事費									昭和設備 株式会社	4-001	2024/05/23
	耐衝撃性硬質塩ビ管(屋外)	HIVP 20	21	m	21	m	13,440	13,440		昭和設備 株式会社	4-001	2024/05/23
	根切り埋戻し費		1	式	1	式	26,000	26,000		昭和設備 株式会社	4-001	2024/05/23
	消耗品雑材料費		1	式	1	式	1,136	1,136		昭和設備 株式会社	4-001	2024/05/23
	[小計]						87,000	87,000		昭和設備 株式会社	4-001	2024/05/23

No	項目	規格・摘要	実行数量	単位	注文数量	単位	実行金額	注文金額	予算残高	発注先	注文No	注文日
	配管材料費									昭和設備 株式会社	4-001	2024/05/23
	架橋ポリエチレン管	13A	19	m	19	m	12,160	12,160		昭和設備 株式会社	4-001	2024/05/23
	配管用継手材料費		1	式	1	式	9,500	9,500		昭和設備 株式会社	4-001	2024/05/23
	管支持金物		1	式	1	式	1,000	1,000		昭和設備 株式会社	4-001	2024/05/23
										昭和設備 株式会社	4-001	2024/05/23
	配管工事費									昭和設備 株式会社	4-001	2024/05/23
	架橋ポリエチレン管	13A	19	m	19	m	12,160	12,160		昭和設備 株式会社	4-001	2024/05/23
	消耗品雑材料費		1	式	1	式	1,180	1,180		昭和設備 株式会社	4-001	2024/05/23
	[小計]						36,000	36,000		昭和設備 株式会社	4-001	2024/05/23

No	項目	規格・摘要	実行数量	単位	注文数量	単位	実行金額	注文金額	予算残高	発注先	注文No	注文日
	配管材料費											
	硬質塩ビ管	VU100	44	m			19,184		19,184			
	硬質塩ビ管	VU75	20	m			6,040		6,040			
	硬質塩ビ管	VU50	15	m			2,535		2,535			
	配管用継手材料費		1	式			22,000		22,000			
	管支持金物		1	式			7,000		7,000			
	小口径汚水柵	100-150	3	組			9,000		9,000			
	トラップ柵	300	2	組			5,600		5,600			
	雨水柵	300	4	組			9,200		9,200			
	屋内配管工事費											
	硬質塩ビ管(屋内)	VU75	2	m			6,384		6,384			
	硬質塩ビ管(屋内)	VU50	13	m			27,664		27,664			
	屋外配管工事費											
	硬質塩ビ管(屋外)	VU100	44	m			113,696		113,696			
	硬質塩ビ管(屋外)	VU75	18	m			35,568		35,568			
	硬質塩ビ管(屋外)	VU50	2	m			2,736		2,736			
	小口径汚水柵取付費	100-150	3	ヶ所			14,400		14,400			
	トラップ柵取付費	300	2	ヶ所			9,600		9,600			
	雨水柵取付費	300	4	ヶ所			19,200		19,200			
	消耗品雑材料費		1	式			14,193		14,193			
	[小計]						324,000		324,000			

衛生器具設備工事

集計日：2024/06/30

No	項目	規格・摘要	実行 数量	単位	注文 数量	単位	実行金額	注文金額	予算残高	発注先	注文No	注文日
	ガーデンパン及び水栓柱	W=450, 900L	1	組	1	組	10,000	10,000		○×建設 株式会社	4-002	2024/05/24
	ガーデンパン及び水栓柱取付費		1	組	1	組	4,800	4,800		○×建設 株式会社	4-002	2024/05/24
	散水栓	散水栓BOX, T27NH13	1	組	1	組	2,925	2,925		○×建設 株式会社	4-002	2024/05/24
	散水栓取付費	散水栓BOX, T27NH13	1	組	1	組	4,000	4,000		○×建設 株式会社	4-002	2024/05/24
	洗濯機用水栓取付費		1	個	1	個	3,200	3,200		○×建設 株式会社	4-002	2024/05/24
	洗濯機パン取付費		1	個	1	個	8,000	8,000		○×建設 株式会社	4-002	2024/05/24
	洋風便器取付費		1	組	1	組	11,200	11,200		○×建設 株式会社	4-002	2024/05/24
	紙巻器取付費		1	個	1	個	2,000	2,000		○×建設 株式会社	4-002	2024/05/24
	洗面化粧台取付費		1	組	1	組	8,000	8,000		○×建設 株式会社	4-002	2024/05/24
	ユニットバス接続費		1	台	1	台	6,400	6,400		○×建設 株式会社	4-002	2024/05/24
	流し台接続費		1	組	1	組	4,000	4,000		○×建設 株式会社	4-002	2024/05/24
	エコキュート取付費		1	台	1	台	20,000	20,000		○×建設 株式会社	4-002	2024/05/24
	消耗品雑材料費		1	式	1	式	8,475	8,475		○×建設 株式会社	4-002	2024/05/24
	[小 計]						93,000	93,000		○×建設 株式会社	4-002	2024/05/24

No	項目	規格・摘要	実行 数量	単位	注文 数量	単位	実行金額	注文金額	予算残高	発注先	注文No	注文日
	配管材料費											
	VP用ボール式ボール分水栓	75X20	1	個			8,492		8,492			
	伸縮可とう継手	20	4	個			14,400		14,400			
	逆止弁付ボール止水栓	20	1	個			7,833		7,833			
	メーターBOX	20	1	個			4,800		4,800			
	ブロック		2	個			200		200			
	SGP-VB	20	3	m			2,289		2,289			
	HIVP	20	2	m			312		312			
	配管工事費											
	分岐掘削工	75X20	1	ヶ所			29,500		29,500			
	分水栓取付工	75X20	1	ヶ所			2,490		2,490			
	管布設工（全面入替）	H=0.6 20	2	m			11,800		11,800			
	布設工	SGP-VB 20	3	m			8,640		8,640			
	ポリスリーブ取付工	75	1	ヶ所			390		390			
	止水栓取付工（BOX据付を含む）	20	1	ヶ所			1,500		1,500			
	擁壁穴明け費		2	ヶ所			4,800		4,800			
	保温工事費		1	式			4,000		4,000			
	埋設シート設置工		1	m			220		220			
	舗装切断工		4	m			1,440		1,440			
	舗装撤去工		1	式			3,200		3,200			
	舗装処理費		1	式			1,200		1,200			
	交通整理員		1	人工			12,000		12,000			
	消耗品雑材料費		1	式			3,194		3,194			
	占用届		1	件			4,300		4,300			
	[小 計]						127,000		127,000			