

# 実行予算書


集計日:2024/06/30

No	4	見積日	2024/5/15						
状況	契約	担当者	昭和 一郎						
顧客名	甲府建設株式会社 御中								
見積先	甲府 二郎 様								
工事名	サンプル設備工事								
工事場所	山梨県甲府市								
	見積金額	実行予算	注文金額	予算残高	実行粗利益	利益率	注文粗利益	利益率	
工事計	791,346	740,000	216,000	524,000	51,346	6	575,346	73	
法定福利費	26,836	25,094							
税抜金額	818,182	765,094	216,000	549,094	53,088	6	602,182	74	
消費税	81,818	76,509	21,600						
税後値引									
税込金額	900,000	841,603	237,600	604,003	58,397	6	662,400	74	
No	項目	規格・摘要	実行数	単位	注文数	単位	実行金額	注文金額	予算残高
	給水設備工事		1	式			87,000	87,000	
	給湯設備工事		1	式			36,000	36,000	
	排水設備工事		1	式			324,000		324,000
	衛生器具設備工事		1	式			93,000	93,000	
	給水管引込工事		1	式			127,000		127,000
	現場雑費		1	式			7,000		7,000
	諸経費	上、下水道申請費を含む	1	式			66,000		66,000
※	別途費用								
	水道利用加入金	136,500円							
	設計審査手数料・竣工検査手数料	8,700円							
	[値引]								
	[工事計]						740,000	216,000	524,000
	[法定福利費]						25,094		

ダンゴ建設株式会社

集計日:2024/06/30

No	項目	規格・摘要	実行数	単位	注文数	単位	実行金額	注文金額	予算残高
	[合計]						765,094	216,000	549,094
	[消費税]						76,509	21,600	
	[税込み合計]						841,603	237,600	604,003

No	項目	規格・摘要	実行数	単位	注文数	単位	実行金額	注文金額	予算残高
	配管材料費								
	耐衝撃性硬質塩ビ管	HIVP20	24	m	22	m	3,542	3,542	
	耐衝撃性硬質塩ビ管	HIVP13	12	m	12	m	1,080	1,080	
	架橋ポリエチレン管	13A 保温厚3mm	24	m	24	m	5,568	5,568	
	配管用継手材料費		1	式	1	式	18,000	18,000	
	管支持金物		1	式	1	式	1,810	1,810	
	屋内配管工事費								
	耐衝撃性硬質塩ビ管(屋内)	HIVP 20	1	m	1	m	1,064	1,064	
	架橋ポリエチレン管	13A	24	m	24	m	15,360	15,360	
	屋外配管工事費								
	耐衝撃性硬質塩ビ管(屋外)	HIVP 20	23	m	21	m	13,440	13,440	
	根切り埋戻し費		1	式	1	式	26,000	26,000	
	消耗品雑材料費		1	式	1	式	1,136	1,136	
	[小計]						87,000	87,000	

## 給湯設備工事

集計日:2024/06/30

No	項目	規格・摘要	実行数	単位	注文数	単位	実行金額	注文金額	予算残高
	配管材料費								
	架橋ポリエチレン管	13A	19	m	19	m	12,160	12,160	
	配管用継手材料費		1	式	1	式	9,500	9,500	
	管支持金物		1	式	1	式	1,000	1,000	
	配管工事費								
	架橋ポリエチレン管	13A	19	m	19	m	12,160	12,160	
	消耗品雑材料費		1	式	1	式	1,180	1,180	
	[小計]						36,000	36,000	

## 排水設備工事

集計日:2024/06/30

No	項目	規格・摘要	実行数	単位	注文数	単位	実行金額	注文金額	予算残高
	配管材料費								
	硬質塩ビ管	VU100	44	m			19,184		19,184
	硬質塩ビ管	VU75	20	m			6,040		6,040
	硬質塩ビ管	VU50	15	m			2,535		2,535
	配管用継手材料費		1	式			22,000		22,000
	管支持金物		1	式			7,000		7,000
	小口径汚水柵	100-150	3	組			9,000		9,000
	トラップ柵	300	2	組			5,600		5,600
	雨水柵	300	4	組			9,200		9,200
	屋内配管工事費								
	硬質塩ビ管(屋内)	VU75	2	m			6,384		6,384
	硬質塩ビ管(屋内)	VU50	13	m			27,664		27,664
	屋外配管工事費								
	硬質塩ビ管(屋外)	VU100	44	m			113,696		113,696
	硬質塩ビ管(屋外)	VU75	18	m			35,568		35,568
	硬質塩ビ管(屋外)	VU50	2	m			2,736		2,736
	小口径汚水柵取付費	100-150	3	ヶ所			14,400		14,400
	トラップ柵取付費	300	2	ヶ所			9,600		9,600
	雨水柵取付費	300	4	ヶ所			19,200		19,200
	消耗品雑材料費		1	式			14,193		14,193
	[小計]						324,000		324,000

衛生器具設備工事

集計日:2024/06/30

No	項目	規格・摘要	実行数	単位	注文数	単位	実行金額	注文金額	予算残高
	ガーデンパン及び水栓柱	W=450, 900L	1	組	1	組	10,000	10,000	
	ガーデンパン及び水栓柱取付費		1	組	1	組	4,800	4,800	
	散水栓	散水栓BOX, T27NH13	1	組	1	組	2,925	2,925	
	散水栓取付費	散水栓BOX, T27NH13	1	組	1	組	4,000	4,000	
	洗濯機用水栓取付費		1	個	1	個	3,200	3,200	
	洗濯機パン取付費		1	個	1	個	8,000	8,000	
	洋風便器取付費		1	組	1	組	11,200	11,200	
	紙巻器取付費		1	個	1	個	2,000	2,000	
	洗面化粧台取付費		1	組	1	組	8,000	8,000	
	ユニットバス接続費		1	台	1	台	6,400	6,400	
	流し台接続費		1	組	1	組	4,000	4,000	
	エコキュート取付費		1	台	1	台	20,000	20,000	
	消耗品雑材料費		1	式	1	式	8,475	8,475	
	[小計]						93,000	93,000	

## 給水管引込工事

集計日:2024/06/30

No	項目	規格・摘要	実行数	単位	注文数	単位	実行金額	注文金額	予算残高
	配管材料費								
	VP用ボール式ボール分水栓	75X20	1	個			8,492		8,492
	伸縮可とう継手	20	4	個			14,400		14,400
	逆止弁付ボール止水栓	20	1	個			7,833		7,833
	メーターBOX	20	1	個			4,800		4,800
	ブロック		2	個			200		200
	SGP-VB	20	3	m			2,289		2,289
	HIVP	20	2	m			312		312
	配管工事費								
	分岐掘削工	75X20	1	ヶ所			29,500		29,500
	分水栓取付工	75X20	1	ヶ所			2,490		2,490
	管布設工(全面入替)	H=0.6 20	2	m			11,800		11,800
	布設工	SGP-VB 20	3	m			8,640		8,640
	ポリスリーブ取付工	75	1	ヶ所			390		390
	止水栓取付工(BOX据付を含む)	20	1	ヶ所			1,500		1,500
	擁壁穴明け費		2	ヶ所			4,800		4,800
	保温工事費		1	式			4,000		4,000
	埋設シート設置工		1	m			220		220
	舗装切断工		4	m			1,440		1,440
	舗装撤去工		1	式			3,200		3,200
	舗装処理費		1	式			1,200		1,200
	交通整理員		1	人工			12,000		12,000
	消耗品雑材料費		1	式			3,194		3,194
	占用届		1	件			4,300		4,300
	[小計]						127,000		127,000